



No.: E-24740/SE/AIIMS RAIPUR/2026-27/LPC/04

Date: 27/06/2026

QUOTATION NOTICE

Inviting quotations for the "Provisioning of Power Supply for installation of CT scan at the department of Radio diagnosis Trauma Ground Floor AIIMS, Raipur". Sealed quotations are invited from the eligible and registered contractors of appropriate list of CPWD /M.E.S. /BSNL (Construction) /Railway /C.G. P.W.D having valid electrical license, GST No. /relevant documents for said work at AIIMS Raipur and should be submitted to office of the Superintending Engineer, 2nd Floor, A-Block, Administrative Building, Gate no.-5, Tatibandh, AIIMS, Raipur up to 3:00 pm on 03.07.2026 item description as per detailed below:

S.No.	ITEM DESCRIPTION	UNIT	QTY	RATE	AMOUNT
1	Supplying & installing following size of perforated pre-painted M.S. cable trays with perforation not more than 17.5%, in convenient sections, jointing with connector, suspended from the ceiling with the M.S. suspenders including bolts & nuts, painting suspenders etc as required.				
1.1	150 mm width X 50 mm depth X 1.6 mm thickness	Meter	81.00	686.00	55,566.00
2	Supplying & installing following size of perforated pre-painted M.S. cable trays bends with perforation not more than 17.5%, in convenient sections, jointing with connector, suspended from the ceiling with the M.S. suspenders including bolts & nuts, painting suspenders etc. as required.				
2.1	150 mm width X 50 mm depth X 1.6 mm thickness	Each	14.00	1,105.00	15,470.00
3	Providing and fixing 25 mm X 5 mm GI strip on surface or in recess for connections etc. as required.	Meter	140.00	287.00	40,180.00
4	Laying of one number PVC insulated and PVC sheathed / XLPE power cable of 1.1 KV grade of following size direct in ground including excavation, sand cushioning, protective covering and refilling the trench etc as required.				
4.1	Above 185 sq. mm and upto 400 sq. mm	Meter	24.00	564.00	13,536.00
5	Laying of one number additional PVC insulated and PVC sheathed / XLPE power cable of 1.1 KV grade of following size direct in ground in the same trench in one tier horizontal formation including excavation, sand cushioning, protective covering and refilling the trench etc as required.				
5.1	Above 185 sq. mm and upto 400 sq. mm	Meter	24.00	423.00	10,152.00
6	Laying & Fixing of one number PVC insulated and PVC sheathed/ XLPE power cable of 1.1kV grade of following size on wall surface as required				
6.1	Above 185 sq.mm and upto 400 sq.mm (Clamped with 40x3mm MS flat clamp)	Meter	284.00	271.00	76,964.00
7	Laying & Fixing of one number PVC insulated and PVC sheathed/ XLPE power cable of 1.1kV grade of following size on cable tray as required				
7.1	Above 35 sq.mm and upto 95 sq.mm (Clamped with 25x3mm MS flat clamp)	Meter	240.00	109.00	26,160.00
7.2	Above 185 sq.mm and upto 400 sq.mm (Clamped with 40x3mm MS flat clamp)	Meter	98.00	226.00	22,148.00

S.No.	ITEM DESCRIPTION	UNIT	QTY	RATE	AMOUNT
8	Supplying and fixing cable route marker with 10 cm X 10 cm X 5 mm thick G.I. plate with inscription there on, bolted /welded to 35 mm X 35 mm X 6 mm angle iron, 60 cm long and fixing the same in ground as required.	Each	3.00	598.00	1,794.00
9	Supplying & making end termination with brass compression gland and aluminium lugs for following size of PVC insulated and PVC sheathed / XLPE Armoured cable aluminium conductor of 1.1kV grade as required.				
9.1	3½ X 70 sq. mm (38mm)	Each	1.00	542.00	542.00
9.2	3½ X 95 sq. mm (45mm)	Each	1.00	684.00	684.00
9.3	3.5 X 240 sq.mm (62MM)	Each	4.00	1,160.00	4,640.00
10	Providing and fixing 630A, 55KA FPMCCB Ics=100% Icu and Operational Voltage 690V, rating and breaking capacity and pole MCCB with thermomagnetic release, along with terminal spreaders, extended rotary handle, Multifunction meter, Indicator Lamps, cable, CTs & TBs in existing cubicle panel board including drilling holes in cubicle panel, making connections, etc. as required.	Set	1.00	1,39,453.00	1,39,453.00
11	Relocation & fixing of Existing 400A incomer Floor panel along with termination of cable etc. as required.	Set	1.00	13,706.00	13,706.00
12	Dismantling aluminium/ Gypsum partitions, doors, windows, fixed glazing and false ceiling including disposal of unserviceable material and stacking of serviceable material within 50 meters lead as directed by Engineer-in-charge.	Sq.mm.	160.00	54.83	8,772.80
13	Disposal of building rubbish / malba / similar unserviceable, dismantled or waste materials by mechanical means, including loading, transporting, unloading to approved municipal dumping ground or as approved by Engineer-in-charge, beyond 50 m initial lead, for all leads including all lifts involved.	cum	7.00	256.82	1,797.74
				Total	4,31,565.54
				Say	4,31,566.00
				Percentage on above amount (+above/- below)	_____ %

Terms & Conditions: -

1. Percentage above or below to the estimated amount should be clearly mentioned.
2. Work duration – within 15 days from the date of issue of work Order.
3. Price should be FOR Destination basis.
4. LD @ 0.5% of delayed supply per week or part of week for delayed work with supply, subject to maximum up to 10%. After expiry of service period service cannot be accepted without extension of service period.
5. Quotation No/Name and Due date of opening must be written on cover top of the envelope.
6. GST rates applicable on your quoted item may please be confirmed.
7. 100% payment against final completion of work & satisfaction of Engineer-In-Charge.
8. Lowest Price L1 will be decided on Total amount basis.
9. The GST registration details may please be furnished.
10. Validity of offer should not be less than 90 days
11. No Payment will be entertained.
12. RTGS detail required for payment purpose.
13. Expenditure will be debitible to GIA-general.
14. AIIMS Raipur reserves the right to place the order for full or part quantity to one or more items.

Superintending Engineer
AIIMS Raipur (C.G.)

List of Mandatory Documents to be submitted by the bidders

1	Enlistment Order for the Contractor
2	EMD amounting ₹ 9000/- to be submitted in the form of an account payee demand draft, fixed deposit receipt from a commercial bank, bank guarantee issued/ confirmed from any of the commercial bank in India in favour of AIIMS, Raipur
3	GST Registration Certificate
4	valid electrical contractor license

Superintending Engineer
AIIMS Raipur (C.G.)